BUREAU OF SANITARY ENGINEERING.

Notification, dated 22nd June 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Sanitary Engineer, Bureau of Sanitary Engineering, Bangalore, up to 2 P.M. on 17th July 1933, for laying the pipe line from the Soap Factory to Old Public Offices Main Sewer for leading off the sewage from Soap Factory and other Public Buildings, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of September 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Sanitary Engineer's Office, between the hours of 11 A.M. to 5 P.M. on all office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Sanitary Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Pomissory Notes, as earnest money, and be superscribed "Tender for laying the pipe line from the Soap Factory to Old Public Offices main sewer for leading off the sewage from Soap Factory and other Public Buildings, Bangalore," in default of which the tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Sanitary Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Sanitary Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Charges on account of scaffolding materials, implements for setting out, barricading, clearing site, supply of water, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Sanitary Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Executive Sanitary Engineer will be final and legally binding.

Abstract estimate of quantities of work to be done for laying the pipe line from the Soap Factory to Old Public Offices main sewer for leading off the sewage from Soap Factory and other Public Buildings, Bangalore.

Particulars	Unit	Quantity	Rate
			Rs. a. p.
I. Earthwork excavation for trenches for laying the pipe line, including refilling trenches in layers of 1' watering and tamping to restore the surface to original ground level and forming sides, including cost of barricading and lighting and keeping watch for preventing accidents either by day or night, the contractor being responsible for any accident and restoring the surface of filled up trench in case of settlement. The excavation should be correct to levels and gradient given and in any case of extra depth excavated beyond this the contractor will restor the surface to correct level by filling up with surki concrete at his own cost.—			
(i) Gravelly soil	C.yds.	1,057	
(ii) Soft Rock	,,	301	
(iii) Hard Rock	,,	301	
II. Laying and jointing stoneware pipes with 1 to 1 cement mortar with necessary yarn caulking and finishing the joint including the cost of stoneware pipes of approved quality with perfect glaze and absolutely straight and [illegible] flow in the make and including all charges			

	Particulars	Unit	Quantity	Rate
	of testing the pipe line before the closing of the trench for pipes of sizes as in following :—			Rs. a. p.
	7" diameter	R.ft.	889	
	6" "	"	2,023	
	4" "	"	340	
	The pipe line will be kept open for the inspection of each joint by the Executive Sanitary Engineer or his representative and will not be closed without his permission.	..	..	
III.	Constructing manholes of 4 ft. diameter including earthwork, excavation, correct to the required dimension, cement concrete bed of one foot depth and 6¾ ft. diameter, side walls of 1½ foot thick of wire-cut brick in cement mortar 1 to 5, if necessary taper for fixing the manhole frame including the cost of cast iron manhole cover and frame of 2 cwt. and of design to be seen at the office and necessary number of cast iron steps of the standard design, making drains with cement concrete and cement plaster, ¾ of the depth of the pipe drain joining it and with 4" slope from side walls to drain and cement plastering ½" thick inside the manhole all over with 1 to 3 cement mortar, etc., complete of depths as in the following :—			
	Upto 2 feet depth	No.	3	
	2' to 3' depth	"	3	
	3' to 4' "	"	4	
	4' to 5' "	"	4	
	5' to 6' "	"	1	
	6' to 7' "	"	1	
	7' to 8' "	"	1	
	8' to 9' "	"	1	
IV.	Providing house connections including the cost of 6" x 4" stoneware gully trap with cast iron grating and 4" diameter stoneware pipes and junction pipes on sub-main line, if necessary, and constructing cisterns with cast iron hinged lid and frame of 14" x 10" complete ..	"	5	
V.	Constructing ventilating shafts with 4" boiler tube of 16 ft. height, masonry support including cement plastering to it and cost of cast iron bend and pipes up to manhole and fixing complete	"	1	

B. R. GARUDACHAR,
Executive Sanitary Engineer

MYSORE RAILWAYS.

Dated 20th June 1933.

TENDERS FOR THE CONTRACT OF INDIAN REFRESHMEMT ROOM ATTACHED TO RAILWAY CENTRAL OFFICES AT MYSORE.

Tenders are invited till 15th July 1933 for running the above Refreshment Room for the convenience of the Staff from 1st July 1933 to 30th June 1935.

The tenderer should clearly specify the amount that he is prepared to pay for the right and also the rate at which the different items of refreshments, etc., will be sold. The tender should be accompanied by an earnest money of Rs. 25 in cash or currency notes. The earnest money will be returned to the unsuccessful tenderer and detained in the case of successful tenderer as earnest, till the end of contract.

The tenders sealed and superscribed " Tenders for Indian Refreshment Room at Mysore Railway Central Offices," should be sent so as to reach the undersigned on the 15th July 1933 at 2 P.M.

The Railway Administration do not bind themselves to accept the highest or any tender or assign any reason for rejecting the tender.

The successful tenderer must pay the amount of contract within seven days of acceptance of the contract and execute an agreement failing which the right will be resold at his risk.

The successful tenderer must be ready to accept any fine or penalty that the Executive Engineer, Mysore Railways, may impose upon him for selling any preparation or exhibition thereof in the Refreshment Room which may be considered to be injurious to [illegible]